No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	CONSTRUCTING COMPOUND WALL.				
1	E. W. excavation foundation	C.yd.	..	8	
2	Size tone in mud	C.ft.	..	221	
3	Burnt brick in mud	,,	..	327	
4	Plastering with mortar	Sqr.	..	9·82	
5	Coping with brick in mud and plastering with mortar	R.ft.	..	98	
6	Providing wicket gate for the opening in compound including fixing labs	No.	..	2	
	CONSTRUCTING BATH ROOM.				
1	E. W. excavation foundation	C.yd.	..	6	
2	Size ton in mud	C.ft.	..	158	
3	Burnt brick in clay	,,	..	569	
4	Plastering with mortar	Sqr.	..	11·42	
5	T. W. work wrought and put up with wood oiling ..	C.ft.	..	8·72	
6	Roofing with 1st Class Mangalore Tiles on teak reepers	Sqr.	..	2·07	
7	Binding wall over roof	R.ft.	..	41	
8	Cornice at ends	,,	..	18	
9	Cement concrete on 4" lime concrete and cement plastering	Sqr.	..	1·20	
10	Constructing sinks in bathroom	No.	..	2	
11	Constructing chimney in bathroom	,,	..	2	

M. K. RAJAM IYENGAR,
Executive Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification dated 16th February 1940,

The attention of the public is hereby invited to the detailed notification, calling for tenders for constructing an R.C.C. tank of 1,00,000 gallons capacity as per specification near the New Mental Hospital, Bangalore, published in pages 634-635, Part VI of the *Mysore Gazette*, dated 21st March 1940.

Last date of receipt of the tender is 3 P.M. on the 6th April 1940. Each tender should accompany with a duplicate challan for having credited the deposit amount of Rs. 750 into the treasury under "17 (a) P. W. Deposits."

M. K. NARASIMHA IYER,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 30th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 19th April 1940, for restoring Ballagere tank, Reg. No. 101 of Nelamangala Taluk.

2. Tenders in the prescribed form obtainable on payment of Re. 0-4-0 per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and be superscribed as "Tender for Restoring Ballagere Tank, Reg. No. 101 of Nelamangala Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 200 under "17 (a) P. W. Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 19th April 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful

tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of September 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 1-4-0 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for restoring Bellagere Tank, Nelamangala Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.			
1	Earthwork to bund including watering and tamping with the required lead and lift	C.yd.	0 3 0	6,743		
2	Turfing the slopes of the bund and watering till it is satisfactory	S.yd.	0 0 10	4,706		
3	Removing and resetting old stone revetment with new jelly backing and jelly wedging, including the required lead and lift, etc.	C.yd.	0 10 0	226		
4	New stone work with jelly backing and jelly wedging, including the required lead and lift, etc.	,,	1 2 0	873		
5	Providing and fixing new grade stones on bed slabs, including chiselling, figures painting and figuring	Each	2 0 0	18		
6	Do Index stones	,,	0 6 0	18		
7	Do B. M. stones on bed slabs, including, chiselling, figures painting and figuring etc., complete	,,	2 8 0	2		
8	Providing and fixing gauge stone with Masonry works, on a bed slab, including, chiselling, figures, painting and figuring, etc., complete	,,	14 0 0	1		
9	Register No. stone on a bed slab including, chiselling figures, painting and figuring, etc.	,,	2 8 0	1		
10	Jungle clearing, with removal of roots ..	Grade	1 0 0	17		
11	Cutting grips and steps	,,	1 8 0	17		
12	Removal of ant hills and filling with sand ..	Each	0 8 0	5		
	EXTENDING THE WASTE WEIR BY 100 FEET.					
1	Earthwork excavation for body wall and returns and using the same for the flank bund with lead and lift, etc. ..	C.yd.	0 3 0	173		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	362		
3	Size stone in surki mortar	,,	0 4 0	327		
4	Burnt stone slabs dressed one line and fixed in surki mortar	S.ft.	0 4 6	195		
5	Cement pointing	Sqr.	3 0 0	4.24		
6	Rough stone work with new jelly backing, jelly wedging with required lead and lift, etc.	C.yd.	1 2 0	201		
	SLUICE.					
1	Earthwork cut opening the bund and refilling the same with watering and tamping ..	C.yd.	0 6 0	250		
2	Earthwork excavating for foundation and using the spoil to the bund with lead and lift	,,	0 3 0	150		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.			
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	100		
4	Size stone in surki mortar	,,	0 4 0	75		
5	Burnt brick in surki morta	,,	0 4 6	50		
6	Burnt stone slabs one line dressed and fixed in surki mortar	S.ft.	0 4 6	100		
7	Plastering with surki mortar	Sqr.	3 8 0	5.00		
8	Cutting holes in the slabs	Each	0 10 0	2		
9	Providing plug and rod with locking arrangement	,,	12 0 0	1		

N. LAKSHMINARASIMIAH,
Executive Engineer

KOLAR DIVISION.

Notification dated 28th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd April 1940, for restoring Purahalli Devarkere, unrestored Major Tank. Reg. No. 257/681 of Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Purahalli Devarkere," The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 295 paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd April 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.